

## Sault Ste. Marie Canal National Historic Site

Northern Ontario Field Unit Parks Canada Agency

# 511 **SSM** POWERHOUSE STRUCTURAL STABILIZATION PROJECT

## PASSIVE GROUND WATER MANAGEMENT

## PROJECT DRAWINGS

Issued For Tender Date: July 2021

Prepared For:

Northern Ontario Field Unit

Prepared By: WSP Canada Inc. Project Consultant





## LIST OF DRAWINGS

### PROJECT DRAWINGS

- PENSTOCK CONCRETE RESERVOIR AND VALVE CHAMBER CROSS-SECTIONS REMOVALS
- PROPOSED PENSTOCK CONCRETE RESERVOIR INTERIOR FLOOR/FOOTINGS/FOUNDATION
- PROPOSED PENSTOCK CONCRETE RESERVOIR CROSS-SECTIONS
- PROPOSED PENSTOCK CONCRETE RESERVOIR CROSS-SECTIONS, FOOTING/FOUNDATION
- PROPOSED CONTEMPORARY VALVE CHAMBER SECTION/DETAILS
- PROPOSED CONTEMPORARY VALVE CHAMBER SECTION/DETAILS

- PROPOSED REDI-ROCK WALL ELEVATIONS/SECTIONS/DETAILS

APPENDIX-A: AS FOUND DRAWINGS AS OF COMPLETION OF SANITARY SYSTEM IMPROVEMENT- FOR REFERENCE PURPOSE ONLY

CONSULTANT:



1345 ROSEMOUNT AVENUE CORNWALL ONTARIO CANADA K6J 3E5 TEL.: 613-933-5602 | FAX: 705-936-0335 | WWW.WSP.COM WSP-5P301-15-0001-001 (WSP# 151-06165-14)



Parcs

Canada

- 1. DRAWINGS TO BE READ IN CONJUNCTION WITH THE PROJECT SPECIFICATIONS AND REFERENCE DRAWINGS.
- 2. NOTIFY DEPARTMENTAL REPRESENTATIVE IF ANY DISCREPANCIES ARE FOUND BETWEEN NOTES IN THIS SET OF DRAWINGS AND THE SPECIFICATIONS.
- 3. IN CASE OF CONFLICTING INFORMATION BETWEEN CONTRACT DRAWINGS AND SPECIFICATIONS, THE MORE STRINGENT SHALL GOVERN OR CONTRACTOR MUST SEEK CLARIFICATION IN WRITING FROM DEPARTMENTAL REPRESENTATIVE.
- 4. ALL WORK IS TO CONFORM TO LATEST EDITION OF THE NATIONAL BUILDING CODE OF CANADA AND WITH ALL APPLICABLE CODES
- BEFORE PROCEEDING WITH WORK, VERIFY DIMENSIONS SHOWN ON THE DRAWINGS AND REPORT DISCREPANCIES TO THE DEPARTMENTAL REPRESENTATIVE. REFER TO OTHER DRAWINGS FOR LOCATIONS AND DIMENSIONING OF APPURTENANCES NOT SHOWN ON THE STRUCTURAL DRAWINGS. OBTAIN THE DEPARTMENTAL REPRESENTATIVES' APPROVAL BEFORE MODIFYING WORK TO SUIT EXISTING CONDITIONS WHICH ARE NOT SHOWN ON THE DRAWINGS.
- THE CONTRACTOR SHALL BE RESPONSIBLE TO RELOCATE, FIELD FIT, INSTALL AND PROVIDE ANCILLARY MATERIALS RELATED TO THE INSTALLATION FOR ANY OWNER SUPPLIED EQUIPMENT. ALL OWNER SUPPLIED EQUIPMENT WILL BE AVAILABLE AT THE SAULT STE. MARIE CANAL NHS.
- ALL DIMENSIONS GIVEN ON DRAWINGS ARE IN METRIC SYSTEM UNLESS OTHERWISE NOTED. DO NOT SCALE DRAWINGS.
- 8. THE CONTRACTOR SHALL FACILITATE ALL MATERIAL TESTING REQUIRED BY THE DEPARTMENTAL REPRESENTATIVE AND AS OUTLINED IN THE CONTRACT SPECIFICATIONS. CONTRACTOR TO ORGANIZE AND COORDINATE AS REQUESTED
- 9. THE PROJECT IS LOCATED IN A NATIONAL HISTORIC SITE (NHS) OF CANADA, THEREFORE STANDARDS FOR ENVIRONMENTAL PROTECTION, CULTURAL RESOURCE PROTECTION AND FOR VISUAL AESTHETICS OF FINAL PRODUCT SHALL BE OF THE HIGHEST QUALITY STANDARD. CONTRACT LIMITS SHALL BE STRICTLY ADHERED TO AND CONTRACTOR IS TO TAKE SPECIAL CARE TO MINIMIZE DAMAGE, DISRUPTION, AND PROTECT EXISTING FEATURES OF THE NHS. THE DEPARTMENTAL REPRESENTATIVE OR DELEGATE IS TO BE NOTIFIED IMMEDIATELY IF ANY NATURAL OR CULTURAL RESOURCES OF INTEREST ARE LOCATED DURING CONSTRUCTION.
- 10. ALL WORK IS TO BE CONDUCTED IN ACCORDANCE WITH THE ONTARIO OCCUPATIONAL HEALTH AND SAFETY ACT.
- 11. THE CONTRACTOR SHALL SUBMIT A RISK MANAGEMENT PLAN TO THE DEPARTMENTAL REPRESENTATIVE OR DELEGATE FOR REVIEW. THE CONTRACTOR SHALL MAINTAIN AND CONSTANTLY UPDATE THE PLAN THROUGHOUT THE PROJECT LIFECYCLE.
- 12. ALL STRUCTURES SHALL BE IN CONFORMANCE WITH THE FOLLOWING DESIGN STANDARDS:
- ONTARIO BUILDING CODE (LATEST EDITION)
- NATIONAL BUILDING CODE OF CANADA 2015 (NBCC) OR NEWER IF IN EFFECT
- HANDBOOK OF STEEL CONSTRUCTION (CISC, CSA S16-14)
- CAN/CSA A23.3-14 DESIGN OF CONCRETE STRUCTURES
- 13. ALL ELECTRICAL WORK SHALL CONFORM TO THE ONTARIO ELECTRICAL CODE. CONTRACTOR SHALL ARRANGE, AND PAY FOR ALL ELECTRICAL PERMITS AND ELECTRICAL SAFETY AUTHORITY (ESA) INSPECTIONS.
- 14. ALL CONTRACTOR SUBMITTALS SHALL BE DONE IN S.I. UNITS (METRIC).
- 15. THE CONTRACTOR SHALL SUBMIT A PROJECT SPECIFIC HEALTH AND SAFETY PLAN FOR REVIEW PRIOR TO COMMENCING CONSTRUCTION. THE CONTRACTOR SHALL ONLY PROCEED WITH CONSTRUCTION UPON ACCEPTANCE OF THE PROJECT SPECIFIC HEALTH AND SAFETY PLAN BY THE DEPARTMENTAL REPRESENTATIVE OR DELEGATE.
- 16. THE CONTRACTOR SHALL SUBMIT A DEMOLITION PLAN FOR REVIEW BY THE DEPARTMENTAL REPRESENTATIVE PRIOR TO SITE REMOVALS. THE CONTRACTOR SHALL ONLY PROCEED WITH CONSTRUCTION UPON COMPLETION OF REVIEW OF THE DEMOLITION PLAN BY THE DEPARTMENTAL REPRESENTATIVE OR DELEGATE.
- 17. THE CONTRACTOR SHALL SUBMIT A TEMPORARY PEDESTRIAN CROSSING PLAN FOR REVIEW PRIOR TO COMMENCING CONSTRUCTION FOR ALL STRUCTURES WHERE PUBLIC ACCESS WILL BE IMPACTED DURING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING PEDESTRIAN TRAFFIC SAFE MEANS OF CROSSING DURING CONSTRUCTION AS THE NHS WILL REMAIN OPEN TO THE PUBLIC IN PART OR WHOLE OF THE CONTRACT PERIOD.
- 18. THE CONTRACTOR SHALL MAINTAIN THE WORKSITE IN A TIDY CONDITION AND FREE FROM THE ACCUMULATION OF WASTE PRODUCTS AND DEBRIS
- 19. USE ONLY THE DRAWINGS THAT ARE MARKED "ISSUED FOR CONSTRUCTION" AND WHICH ARE STAMPED BY A PROFESSIONAL ENGINEER LICENSED IN THE PROVINCE OF ONTARIO. CONFIRM WITH THE DEPARTMENTAL REPRESENTATIVE OR DELEGATE.
- 20. ALL SECTIONS, DETAILS AND STATEMENTS NOTED AS "TYPICAL" APPLY TO LIKE/SIMILAR CONDITIONS
- 21. THE CONSULTANT AND THE DEPARTMENTAL REPRESENTATIVE, AT TIMES, WILL CONDUCT INSPECTIONS OF THE WORK TO ENSURE GENERAL CONFORMANCE WITH THE DESIGN DRAWINGS. THIS DOES NOT REPLACE THE CONTRACTOR'S RESPONSIBILITY TO IMPLEMENT AND MAINTAIN A QUALITY CONTROL PROGRAM.
- 22. SUBSTANTIAL COMPLETION OF THE PROJECT WILL NOT BE ISSUED UNTIL AS-BUILT RECORD DRAWINGS HAVE BEEN PROVIDED WITH ALL REQUIRED INFORMATION TO THE SATISFACTION OF THE CONSTRUCTION ADMINISTRATOR.
- 23. THE CONTRACTOR SHALL PROVIDE FOUR (4) COMPLETE SETS OF AS-BUILT RECORD DRAWINGS. ALL CHANGES ARE TO BE MARKED IN RED AND MUST BE CLEAN AND LEGIBLE.
- 24. NO BURNING IS PERMITTED WITHIN THE NATIONAL HISTORIC SITE.
- 25. THE CONTRACTOR SHALL ERECT SILT FENCING ALONG ALL WATER COURSES DURING CONSTRUCTION.
- THE CONTRACTOR SHALL SUBMIT A SEDIMENT AND EROSION CONTROL PLAN PRIOR TO CONSTRUCTION. CONSTRUCTION WORK CAN COMMENCE ONLY AFTER SITE SPECIFIC ENVIRONMENTAL PROTECTION PLAN THAT INCLUDES ACCEPTANCE OF THIS PLAN BY DEPARTMENTAL REPRESENTATIVE OR DELEGATE.
- 27. THE CONTRACTOR SHALL PROVIDE ALL SHOP DRAWINGS IN ACCORDANCE WITH THE CONTRACT SPECIFICATIONS. ALL SHOP DRAWING SUBJECT TO REVIW FROM DEPARTMENTAL REPRESENTATIVE OR DELEGATE.
- 28. ALL WORK WITHIN A 30 METER DISTANCE OF A WATER WAY SHALL ADHERE TO THE FISHERIES ACT. THE CONTRACTOR SHALL
- SUBMIT A WORK PLAN FOR ALL WORK. 29. ALL WORK SHALL CONFORM TO THE ENVIRONMENTAL BASIC IMPACT ANALYSIS (BIA). APPENDIXED TO THE CONTRACT SPECIFICATIONS.
- 30. ITEMS OF WORK THAT THE PARKS CANADA AGENCY WOULD LIKE TO COMPLETE, BUT MAY CHOOSE NOT TO COMPLETE DUE TO BUDGETARY RESTRAINTS, ARE SHOWN AS "PROVISIONAL ITEM". THE CONTRACTOR SHALL PRICE THESE ITEMS ACCORDINGLY AND SHALL NOT CLAIM ANY ANTICIPATED LOSS OF PROFIT OR INCREASED OVERHEAD IF ANY OR ALL OF THESE ITEMS ARE DELETED ALTOGETHER. THE CONTRACTOR SHALL BE NOTIFIED AT THE TIME OF AWARD OF CONTRACT AND THROUGH THE DRAWINGS SET ISSUED FOR CONSTRUCTION UPON AWARD OF CONTRACT IF PARKS CANADA AGENCY WISHES TO PROCEED WITH DELETION OF ANY OF THESE ITEMS.

### REMOVALS

- CONTRACTOR SHALL ERECT TEMPORARY GUARDS (CHAIN LINK OR WELDED WIRE FENCE WITH A MINIMUM HEIGHT OF 1.8m) AROUND EXCAVATION AS PER OBC. GUARDS SHALL REMAIN IN PLACE UNTIL COMPLETION OF CONSTRUCTION.
- VIBRATION MONITORING SHALL BE INSTALLED IN THE POWERHOUSE PRIOR TO ANY REMOVALS.
- 3. ALL REMOVALS ARE TO BE CARRIED OUT WITH PRECAUTIONS FOR THE SAFETY OF THE PUBLIC AND PARKS CANADA'S EMPLOYEES, AND PROPERTY.
- 4. DEMOLITION WORK SHALL BE CARRIED OUT WITHOUT CAUSING OVERSTRESS OR EXCESSIVE DEFLECTION TO ANY PART OF THE EXISTING WORK WHICH IS TO REMAIN. THE CONTRACTOR IS RESPONSIBLE TO MAKE GOOD ANY DAMAGE CAUSED DURING DEMOLITION.
- 5. THE CONSTRUCTION SITE SHALL REMAIN FREE OF ANY DEBRIS AND / OR GARBAGE.
- 6. THE CONTRACTOR IS RESPONSIBLE FOR ALL DISPOSAL/TIPPING FEES.
- 7. THE CONTRACTOR SHALL DISPOSE OF CONSTRUCTION DEBRIS AT LEGALLY DESIGNATED SITES IN ACCORDANCE WITH APPLICABLE LAWS.
- 8. ALL REMOVALS ARE TO BE COMPLETED WITH REFERENCE TO THE CONTRACT DRAWING SPECIFICATIONS.
- STORE ALL STONE FROM WEST AND SOUTH VALVE CHAMBER WALL AT PCA DESIGNATED LOCATION.
- STORE ALL REMOVED SIGNAGE FOR HISTORIC VALVE AT A PCA DESIGNATED LOCATION.
- 11. TAGGING OF SANDSTONE WALL BLOCKS IS NOT REQUIRED DURING REMOVAL AND STORAGE 12. ALL UTILITIES EXPOSED THROUGH HYDROVAC EXCAVATION SHALL BE SUPPORTED FOR DURATION OF CONSTRUCTION WORK. 13. VALVE CHAMBER WALL REMOVAL PROCEDURE WILL FOLLOW A LAYERED "TOP DOWN, OUTSIDE-IN" APPROACH . THE CONTRACTOR
- TOWARDS THE POWERHOUSE WALL. BLOCK WALL REMOVAL PROCEDURES ARE OUTLINED BELOW a) IMPLEMENT PROTECTIVE BUFFER SYSTEM FOR THE POWERHOUSE WALL TO PROTECT THE POWERHOUSE WALL AGAINST EXTERNAL FORCES (FALLING DEBRIS, MACHINERY IMPACT, ETC.).

SHALL REMOVE THE TOP LAYERS OF STONE FURTHEST FROM THE FACE OF THE POWERHOUSE FIRST, WORKING THEIR WAY

- b) SAWCUT AND REMOVE CONCRETE ROOFING SLABS AS SHOWN IN THE REMOVALS PENSTOCK CONCRETE RESERVOIR
- c) SMALLER STONE FILL BENEATH ROOF SLAB TO BE REMOVED WITH MANUAL HYDRAULIC AIR HAMMERS OR BOOM MOUNTED HYDRAULIC BREAKER, MOUNTED ON A MINI-EXCAVATOR CAPABLE OF NAVIGATING THE SPACE BETWEEN THE EXISTING WALLS. IF THE BOOM MOUNTED HYDRAULIC BREAKER IS USED, VIBRATIONS CAUSED BY THE USE OF BREAKER MUST BE MONITORED TO ENSURE VIBRATIONS REMAIN UNDER DESTRUCTIVE LIMITS. REFER TO APPENDIX E "NOISE, VIBRATION AND AMBIENT LIGHT MANAGEMENT COMPONENT PLAN" (2018) OF HPN ENGINEERING'S SITE SPECIFIC ENVIRONMENTAL PLAN FOR VIBRATION
- MONITORING PROTOCOL. d) MORTAR OF THE LARGEST STONES BENEATH THE SMALLER STONE FILL WILL BE CHISELED OFF PRIOR TO REMOVAL EFFORTS. e) BLOCKS LARGER THAN 2 CUBIC METERS, ARE TO BE BROKEN DOWN INTO SMALLER, MORE MANAGEABLE PIECES IF STONES CAN NOT BE FEASIBLY REMOVED AS A WHOLE. APPROVAL MUST BE GRANTED TO BREAK BLOCKS BY A DEPARTMENTAL
- REPRESENTATIVE OR THE CONTRACT ADMINISTRATOR PRIOR TO BREAKING BLOCKS. f) REMOVED BLOCKS SHALL BE PRESERVED AND STORED ON SITE IN A PCA DESIGNATED LOCATION.
- g) CARE MUST BE TAKEN SO AS NOT TO DESTROY THE BLOCKS DURING REMOVAL AND TRANSPORTATION.
- 14. ANY STONES OF 0.5m DIAMETER OR LARGER FOUND DURING HYDROVAC EXCAVATION AROUND PENSTOCK CONCRETE RESERVOIR WALLS IS TO BE REMOVED AND STORED AT A PCA DESIGNATED LOCATION.

#### **EXCAVATION**

- 1. ANY ARTIFACTS UNEARTHED DURING THE WORK SHALL BE LEFT UNTOUCHED UNTIL INSPECTED BY PARKS CANADA. ANY ARTIFACTS SHALL REMAIN THE PROPERTY OF PARKS CANADA.
- 2. ANY SANDSTONE, LIMESTONE, OR LARGE BOULDERS IN EXCESS OF 1.0 CU.METRES SHALL BE LEFT IN THE LAYDOWN AREA. OTHER EXCAVATED MATERIALS SHALL BE HAULED AND DISPOSED OF OFF-SITE.

#### **MATERIALS**

- 1. ALL PROPOSED WORKS SHALL BE CONSTRUCTED WITH NEW MATERIAL ONLY. MATERIALS IDENTIFIED FOR DEMOLITION ARE TO BE REMOVED FROM THE SITE AND PROPERLY DISPOSED OF IN STRICT ACCORDANCE WITH APPLICABLE STANDARDS.
- 2. MATERIAL USED FOR CONSTRUCTION SHALL BE FREE OF ANY DEFECTS.
- 3. THE CONTRACTOR SHALL REPAIR AT THEIR COST ANY DAMAGES AS A RESULT OF CONSTRUCTION THAT IS NOT SPECIFIED FOR REMOVAL. ALL REPAIRS MUST BE COMPLETED TO THE SATISFACTION OF THE DEPARTMENTAL REPRESENTATIVE.
- 4. ALTERNATIVES MAY BE CONSIDERED AFTER CONTRACT AWARD ONLY. SUBMIT PROPOSAL IN WRITING FOR ALTERNATIVE PRODUCTS AND ALLOW FOR RESPONSE TIME OF 7 CALENDAR DAYS FOR DEPARTMENTAL REPRESENTATIVES REVIEW AND APPROVALS. ALTERNATIVES WILL ONLY BE CONSIDERED IF THERE IS A SUBSTANTIVE CREDIT TO THE OWNER, OR THE SPECIFIED MATERIALS WILL CAUSE A SCHEDULE DELAY IMPACTING THE PROJECT CRITICAL PATH.

### CONSTRUCTION SEQUENCING

## 1. CONFIRM BEDROCK ELEVATION WITHIN THE PENSTOCK, ALONG THE WEST PENSTOCK CONCRETE

2.	INSTALL ADDITIONAL TEMPORARY PERIMETER FENCING (AS REQUIRED UNDER OBC COMPLIANCE).
3.	IMPLEMENT VIBRATION MONITORING PROGRAM WITHIN THE POWERHOUSE.
4.	REMOVE ALL PENSTOCK CONCRETE RESERVOIR ROOF PANELS.
5.	HYDROVAC SOIL ALONG THE EXTERIOR OF THE WEST AND NORTH WALLS OF THE PENSTOCK CONCRET
	RESERVOIR TO THE REQUIRED DEPTH AND OFFSET. A MAXIMUM EXCAVATION SLOPE OF 1:1 MUST BE
	MAINTAINED.
6.	RELOCATE EXISTING BELL COMMUNICATIONS LINE TO MOTORHOUSE.

7. SAW CUT ALONG WEST WALL OF POWERHOUSE TO ENSURE ISOLATION FOR DEMOLITION OF VALVE

CHAMBER FLOOR AND SOUTH VALVE CHAMBER WALL. 8. DISASSEMBLE SOUTH AND WEST WALL OF THE EXISTING VALVE CHAMBER. SANDSTONE WALL BLOCKS STORED FOR RE-PURPOSE LATER. 9. INSTALL TEMPORARY SUBMERSIBLE PUMPS FOR DEWATERING AND TREATMENT DURING DEMOLITION. 10. REMOVE BEAMS AND COLUMNS, CONCRETE INLET AND OUTLET FLUMES AND REMAINING CONCRETE

RESERVOIR WALL, AND AT THE LOCATION OF THE NEW SEDIMENTATION MANHOLES.

RESERVOIR. EXISTING FILL TO BE KEPT ON SITE IN A DESIGNATED AREA TO BE REUSED IN THE PENSTOCK CONCRETE RESERVOIR FLOOR SYSTEM. 11. INSTALL SUBMERSIBLE PUMPS IN THE AREA OF THE PROPOSED VALVE CHAMBER TO ADEQUATELY DEWATER THE WORK AREA. INSTALL SUBMERSIBLE PUMPS IN A MANNER THAT ENABLES EASY

FLOOR AND UNDERLYING FILL DOWN TO DESIGNATED DEPTH WITHIN THE PENSTOCK CONCRETE

- REMOVAL POST GROUTING WORKS. 12. PLACE NON-SHRINK CONCRETE GROUT TO FORM BASE FOR NEW CONTEMPORARY VALVE CHAMBER AND VALVE TOWER SUPPORT WALL IN THE DESIGNATED AREA OF THE PENSTOCK CONCRETE RESERVOIR. 13. INSTALL PASSIVE WATER MANAGEMENT PIPING ALONG THE SOUTH WALL OF THE PENSTOCK CONCRETE C5.1
- RESERVOIR AND WEST WALL OF THE POWERHOUSE C/W CONNECTION INTO SEDIMENTATION MANHOLES AND ASSOCIATED TREATMENT STATION. C4.0 14. INSTALL NEW CAST-IN-PLACE CONCRETE VALVE CHAMBER
- 15. INSTALL NEW KEYED VALVE TOWER WALL SUPPORT AT SOUTH WEST CORNER OF THE PENSTOCK CONCRETE RESERVOIR.
- 16. INSTALL STEEL PIPING CONNECTION PCA SUPPLIED NEW CONTEMPORARY VALVE. 17. INSTALL CAST-IN-PLACE FOOTING FOR THE PENSTOCK CONCRETE RESERVOIR NORTH WALL. 18. INSTALL CAST-IN-PLACE FOUNDATION FOR FUTURE HYDRO GENERATIONS PROJECT.
- 19. POUR NON-SHRINK FILL FLOOR COMPLETE WITH USEABLE FILL REMOVED IN STEP 10 THROUGHOUT PENSTOCK CONCRETE RESERVOIR FLOOR. 20. INSTALL NORTH AND SOUTH HISTORIC VALVES C/W CAST-IN-PLACE CONCRETE SUPPORTS
- C4.5 21. SUPPLY AND INSTALL 1.83m Ø X 1.83m Ø X 1.52m Ø MANIFOLD TO OUTLET OF CONTEMPORARY VALVE. 22. INSTALL PCA SUPPLIED BLIND FLANGE TO THE 1.83m Ø NORTH LEG OF "Y" PIPE SYSTEM. C4.5 23. SUPPLY AND INSTALL 1.52m Ø STEEL PIPE BETWEEN MANIFOLD AND SOUTH HISTORIC VALVE. C7.0,C7.1 24. INSTALL CAST-IN-PLACE PENSTOCK CONCRETE RESERVOIR NORTH WALL C/W STEEL DOUBLE DOOR
- AND SANDSTONE VENEER ON EXTERIOR FACE OF WALL. C7.0,C7.1 25. INSTALL NEW HOLLOW CORE PENSTOCK CONCRETE RESERVOIR ROOF PANELS WITH CAST-IN PLACE TOP COAT TO MATCH EXISTING.
- C7.2 26. INSTALL CAST-IN-PLACE CONCRETE STAIRS NORTH OF THE POWERHOUSE/PENSTOCK CONCRETE 27. INSTALL REDI-ROCK WALL RETAINING WALL BETWEEN THE NEW STAIRS AND THE PENSTOCK CONCRETE C7.3

RESERVOIR NORTH WALL.

SEQUENCING FOR REVIEW PRIOR TO THE WORK

28. SITE CLEANUP AND RESTORATION. NOTE: THIS CONSTRUCTION SEQUENCE IS A GUIDE ONLY AND IS NOT MEANT TO CONTROL THE CONTRACTOR'S

SEQUENCING OF THE WORK. THE CONTRACTOR SHALL SUBMIT A WORK PLAN AND PROPOSED CONSTRUCTION

### **LEGEND**

**DRAWING REFERENCE** 

C3.0

C1.1

C3.0

C3.0

C3.0

C3.0

C3.0,C3.1

C5.0

C4.0

C4.0,C4.1,C4.2

C4.0,C4.2


C4.0,4.2

C4.0

C4.5

C3.0

		EXISTING EDGE OF CONCRETE
в	В	EXISTING BURIED COMMUNICATION
—— НҮР ——— НҮР —————————————————————————	Нур	EXISTING BURIED HYDRO
	W	EXISTING BURIED WATER
SA	SA	EXISTING BURIED SANITARY
ST	ST	EXISTING BURIED STORM




- **EXISTING SHRUB** EXISTING TREE
- EXISTING BOLLARD EXISTING SANITARY MANHOLE
- EXISTING STORM MANHOLE EXISTING CATCHBASIN
- **EXISTING WATER WELL**
- EXISTING FIRE HYDRANT **EXISTING ELECTRICAL HANDHOLE**
- EXISTING HANDHOLE REFERENCE PHOTO VIEW POINT
- PROPOSED BURIED UTILITY PROPOSED CONCRETE
  - PROPOSED STORM MANHOLE

PROPOSED SANITARY MANHOLE




Gouvernement of Canada


Parks Canada



Parcs Canada Unité de gestion du Nord de l'Ontario



No.	Date	Description	Drawn by Dessiné par	Approved Approuvé
0	21APR20	66% REVIEW	M.CARBONE	D.SPACEK
1	26JUNE20	75% REVIEW	M.CARBONE	D.SPACEK
2	18MAR21	90% REVIEW	M.CARBONE	D.SPACEK
3	25APR21	99% REVIEW	M.CARBONE	D.SPACEK
4	16JULY21	ISSUED FOR TENDER	M.CARBONE	D.SPACEK



A Numéro de detail B Numéro de la feuille

Revision / Revision

Dimensions linéaires en millimétres in millimetres






Project title/Titre du projet


511SSM POWERHOUSE STRUCTURAL STABILIZATION PROJECT

Drawing title/Titre du dessin


GENERAL NOTES /SITE PLAN

Designed by/Concept par J.DICERBO / D.SPAC	CEK	Date MAY 25, 2021
Drawn by/Desinné par M.CARBONE		Date MAY 25, 2021
Checked by/Vérifié par J.DICERBO		Date MAY 25, 2021
Approved by/Approuvé par D.SPACEK		Date MAY 25, 2021
Project No./No du projet 511SSM	Scale/Échelle 1:150	Sheet No./ N°de la feuille
Drawing Set No./N <sup>o</sup> de sér	ie du dessin	C1.1





DEBRIS BENEATH SMALL CONCRETE CHAMBER WITHIN PENSTOCK



**3 REFERENCE PHOTO** 



SITE

NOTE: PHOTO ARE FOR REFERENCE

ONLY. ACTUAL CONDITIONS MAY VARY.

of Canada

KEY PLAN:

SAULT STE. MARIE, ONTARIO

3 25APR21

26JUNE20

1APR20

Date

Project title/Titre du projet

Gouvernement

Parcs Canada

Unité de gestion du Nord de l'Ontario

du Canada

2 REFERENCE PHOTO
C2.0 SCALE: NTS

CONCRETE

PENSTOCK

CONCRETE

RESERVOIR

WITHIN

OUTLET FLUME

CONCRETE SUPPORT COLUMN

CONCRETE

RESERVOIR

WITHIN PENSTOCK




HOLLOW CORE ROOF PANELS WITH CONCRETE TOP COAT COVERING EXISTING PENSTOCK CONCRETE RESERVOIR PENSTOCK CONCRETE RESERVOIR CONCRETE INLET FLUME WITHIN PENSTOCK CONCRETE RESERVOIR

5 REFERENCE PHOTO

EXISTING ACCESS TO

PENSTOCK CONCRETE

RESERVOIR (GRATE AND



CONCRETE INLET FLUME

WITHIN PENSTOCK CONCRETE RESERVOIR





8 REFERENCE PHOTO








11 REFERENCE PHOTO C2.0 SCALE: NTS

REFERENCE PHOTO 13 LOOKING WEST AT CANALMAN'S SHELTER

REFERENCE PHOTO 14 LOOKING NORTHWEST AT GRAVEL ACCESS PATH TO SITE



DRAWING LOCATION REFERENCE PHOTO 1 LOOKING SOUTHEAST AT POWERHOUSE DURING CONSTRUCTION CIRCA 1890 LOOKING EAST AT POWERHOUSE AND HISTORICAL VALVES/PENSTOCK REFERENCE PHOTO 2 LOOKING EAST AT CONCRETE HOLLOW CORE ROOF PANELS COVERING PENSTOCK REFERENCE PHOTO 3 LOOKING SOUTHEAST AT PENSTOCK CONCRETE RESERVOIR ACCESS HATCH WITH **REFERENCE PHOTO 4** WOOD COVER LOOKING UP AT PENSTOCK CONCRETE RESERVOIR ACCESS HATCH AND STEEL **REFERENCE PHOTO 5** GRADING FROM WITHIN THE PENSTOCK CONCRETE RESERVOIR WITHIN PENSTOCK CONCRETE RESERVOIR LOOKING SOUTHEAST AT OUTLET REFERENCE PHOTO 6 CONCRETE FLUMES AND SUPPORT COLUMNS WITHIN PENSTOCK CONCRETE RESERVOIR LOOKING EAST AT CONCRETE OUTLET REFERENCE PHOTO 7 WITHIN PENSTOCK CONCRETE RESERVOIR LOOKING SOUTHWEST AT CONCRETE **REFERENCE PHOTO 8** INLET FLUMES AND EXISTING CONCRETE HOLLOW CORE ROOF PANELS WITHIN PENSTOCK CONCRETE RESERVOIR LOOKING EAST INTO THE SOUTHEAST REFERENCE PHOTO 9 CORNER AT THE SMALL CONCRETE CHAMBER LOOKING SOUTHEAST AT POWERHOUSE WALL AND EXISTING VALVE CHAMBER REFERENCE PHOTO 10 LOOKING SOUTHWEST AT THE EXISTING VALVE CHAMBER PRE-CONSTRUCTION OF REFERENCE PHOTO 11 NEW STORM MANHOLES (2) INSTALLED DECEMBER 2020 FOR PASSIVE WATER MANAGEMENT SYSTEM LOOKING EAST AT PROPOSED VALVE TOWER KEYED SUPPORT WALL AND REFERENCE PHOTO 12 CAST-IN-PLACE CONTEMPORARY VALVE CHAMBER WALL STABILIZATION.

12 REFERENCE DRAWING C4.0 SCALE: NTS **REFERENCE PHOTO TABLE** COMMENT PRIOR TO VALVE CHAMBER CONSTRUCTION PRIOR TO PENSTOCK CONCRETE RESERVOIR CONSTRUCTION- SHOWS CONSTRUCTION OF SOUTH WALL OF VALVE CHAMBER. TO BE REMOVED AND DISPOSED OFF SITE POST VALVE CHAMBER CONSTRUCTION TO BE REMOVED AND DISPOSED OFF SITE REFER TO LIMITS OF EXCAVATION ON DRAWING C3.0 REFER TO LIMITS OF EXCAVATION ON DRAWING C3.0 REFER TO LIMITS OF EXCAVATION ON DRAWING C3.0 REMOVALS TO BE DISPOSED OFF TO BE REMOVED AND DISPOSED OFF SITE CONTRACTOR TO ASSUME SANDSTONE BLOCK TO EXTENT DOWNWARD AND SPAN THE ENGTH OF POWERHOUSE WEST WALL SANITARY LINE IN PHOTO HAS BEEN CONNECTED TO DOWNSTREAM SANITARY MAN HOLE AS PART OF A PREVIOUS CONTRACT (PART A), THE SANITARY LINE LEADING INTO THE POWERHOUSE IS NOW ABANDONED AND CAN BE DELETED. CONCEPTUAL CAD RENDERING OF PROPOSED KEYED WALL TO ASSIST IN MOTOR HOUSE

VISIBLE GRADE DROP AT EDGE OF EXISTING SIDEWALK AND SOD

REFER TO DRAWING 4.0 FOR PROPOSED NEW SIDEWALK AND SOD WORK

EXISTING SURFACE DRAIN LOW LAYING AREA

13 REFERENCE PHOTO C2.0 SCALE: NTS

14 REFERENCE PHOTO C2.0 SCALE: NTS

Dimensions linéaires en millimétres Linear dimensions in millimetres Consultant's Name Nom de l'expert—consei Eng. Stamp Sceau de l'ingénieur

1345 ROSEMOUNT AVENUE

CORNWALL ONTARIO CANADA K6J 3E5
TEL.: 613-933-5602 | FAX: 705-936-0335 | WWW.WSP.COM

WSP-5P301-15-0001-001 (WSP# 151-06165-14)

ISSUED FOR TENDER

99% REVIEW

90% REVIEW

75% REVIEW

66% REVIEW

Revision / Revision

M.CARBONE D.SPACEK

M.CARBONE D.SPACEK

M.CARBONE D.SPACEK

M.CARBONE D.SPACEK

M.CARBONE D.SPACEK

A Numéro de detail

B Numéro de la feuille

D. M. SPACER July 16, 2021

Approved Approuvé

511SSM POWERHOUSE STRUCTURAL STABILIZATION PROJECT

Drawing title/Titre du dessin REFERENCE PHOTOS AND DRAWING

Drawing Set No./Nº de sér	ie du dessin	C1.2
Project No./No du projet 511SSM	Scale/Échelle VARIES	Sheet No./ N <sup>o</sup> de la feuille
Approved by/Approuvé par D.SPACEK		Date MAY 25, 2021
Checked by/Vérifié par J.DICERBO		Date MAY 25, 2021
Drawn by/Desinné par M.CARBONE		Date MAY 25, 2021
Designed by/Concept par J.DICERBO/D.SPAC	CEK	MAY 25, 2021
D1 t (0t		15.





14 REFERENCE PHOTO





SITE

Government of Canada

Parks Canada

Government Gouvernement

du Canada

Parcs Canada

Unité de gestion du Nord de l'Ontario

SAULT STE. MARIE, ONTARIO

KEY PLAN:

16 REFERENCE PHOTO C2.0 SCALE: NTS

13 REFERENCE PHOTO C2.0 SCALE: NTS



WEST WALL OF EXISTING VALVE CHAMBER AND DESIGNATED PARTITION OF NORTH WALL OF NEW SEDIMENTATION MAN PENSTOCK CONCRETE HOLE FOR PASSIVE WATER RESERVOIR TO BE REMOVED MANAGEMENT SYSTEM 1 OF 2 INSTALLED 2020)

PROTECTIVE CONCRETE SLAB/SIDEWALK CAST-IN-PLACE

REFERENCE PHOTO C2.0 SCALE: NTS



NOTE: PHOTO ARE FOR REFERENCE ONLY. ACTUAL CONDITIONS MAY VARY.

ISSUED FOR TENDER

99% REVIEW

90% REVIEW

75% REVIEW

66% REVIEW

17 REFERENCE PHOTO



18 REFERENCE PHOTO



19 REFERENCE PHOTO C2.0 SCALE: NTS



24 REFERENCE DRAWING
C2.0 SCALE: NTS

21 REFERENCE PHOTO C2.0 SCALE: NTS

	22 REFERENCE PHOTO C2.0 SCALE: NTS	23 REFERENCE PHOTO C2.0 SCALE: NTS
	REFERENCE PHOTO	O TABLE
DRAWING	LOCATION	COMMENT
REFERENCE PHOTO 13	LOOKING SOUTHEAST AT POWERHOUSE PRIOR TO INSTALLATION OF MANHOLES FOR PASSIVE WATER MANAGEMENT (2020)	SANDSTONE BLOCK ENCOUNTERED IN FLOOR AREA OF EXISTING VALVE CHAMBER CONTRACTOR TO ASSUME SANDSTONE BLOCK TO BE CONTINUOUS THROUGHOUT EXISTING VALVE CHAMBER FLOOR.
REFERENCE PHOTO 14	LOOKING SOUTHEAST AT POWERHOUSE AFTER INSTALLATION OF SEDIMENTATION MANHOLE (1 OF 2) FOR PASSIVE WATER MANAGEMENT (2020)	SANDSTONE BLOCK ENCOUNTERED IN FLOOR AREA OF EXISTING VALVE CHAMBER APPEARS TO EXTENT TO THE BASE OF THE NEW MAN HOLE.
REFERENCE PHOTO 15	LOOKING SOUTHEAST AT POWERHOUSE AFTER INSTALLATION OF SEDIMENTATION MANHOLES FOR PASSIVE WATER MANAGEMENT AND NEW SANITARY LINE FROM PREVIOUS CONTRACT (2020)	PRECAST MAN HOLE BASE PREDRILLED TO ACCEPT BIG "O' PASSIVE WATER PIPING SYSTEM.
REFERENCE PHOTO 16		HEAVY EQUIPMENT TRAFFIC SHOULD BE MINIMIZED TO AVOID DISRUPTION PIPING, $^3\!4$ " PLY SHOULD BE LAID DOWN TO AVOID MOVEMENT FROM ROTATION OF TRACKED EQUIPMENT.
REFERENCE PHOTO 17	LOOKING WEST AT EXCAVATED AREA BETWEEN THE PENSTOCK CONCRETE RESERVOIR NORTH WALL AND PUBLIC WASHROOM FACILITY.	NOTE SHOULD BE TAKEN TO LOCATION AND MINIMAL COVERAGE OF THE NEW SANITARY PIPE SHOWN (2020), A CONCRETE SIDEWALK HAS BEEN PLACED DIRECT ON TOP OF 4" RIDGID INSULATION RESTING ON SANITARY PIPE.
REFERENCE PHOTO 18	LOOKING SOUTHWEST AT THE POWERHOUSE/PENSTOCK CONCRETE RESERVOIR DURING INSTALLATION OF PASSIVE WATER MANAGEMENT SYSTEM MAN HOLES.	REFER TO LIMITS OF EXCAVATION ON DRAWING C4.0 PLAN VIEW FOR LOCATION
REFERENCE PHOTO 19	LOOKING EAST AT NEW CONCRETE SIDEWALK BETWEEN POWERHOUSE AND STORES BUILDING COVERING NEW SANITARY PIPE (2020)	REFER TO EXISTING CONDITIONS ON DRAWING C2.0
REFERENCE PHOTO 20	LOOKING SOUTHWEST AT THE EXISTING CONDITIONS OF VALVE CHAMBER AFTER THE INSTALLATION OF THE TWO MAN HOLES FOR THE PASSIVE WATER MANAGEMENT SYSTEM (2020)	REFER TO EXISTING CONDITIONS ON DRAWING C2.0
REFERENCE PHOTO 21	LOOKING WEST AT NATIVE SOIL BACKFILL COVERED WITH GEOTEXTILE FROM RECENT GROUND WORK AND INSTALLATION OF NEW SANITARY LINE BETWEEN EXISTING PENSTOCK CONCRETE RESERVOIR AND PUBLIC WASHROOM FACILITY.	NATIVE FILL COVERED WITH GEOTEXTILE PRIOR TO RIPRAP TOPCOAT.
REFERENCE PHOTO 22	LOOKING DOWN IN A SOUTHWESTERLY DIRECTION FROM TOP OF RECENT GROUND WORK LOOKING AT EXPOSED PORTION OF THE PENSTOCK CONCRETE RESERVOIR NORTH WALL TO BE REMOVED.	REFER TO C4.0 FOR LIMITS OF PENSTOCK CONCRETE RESERVOIR NORTH WALL TO BE REMOVED.
REFERENCE PHOTO 23	SANITARY LINE BETWEEN EXISTING PENSTOCK CONCRETE RESERVOIR AND PUBLIC WASHROOM	RIPRAP WILL NEED TO BE REMOVED AND STORE FOR REPURPOSE TO ACCESS NORTH PORTION OF PENSTOCK CONCRETE RESERVOIR WALL TO BE REMOVED. REFER TO C4.0 FOR LIMITS OF PENSTOCK CONCRETE RESERVOIR NORTH WALL TO BE REMOVED.
REFERENCE PHOTO 24	LOOKING SOUTHWEST AT EXISTING CONDITIONS AT THE COMPLETION OF CONSTRUCTION (2020)	REFER TO EXISTING CONDITIONS ON DRAWING C2.0

Revision / Revision A Numéro de detail B Numéro de la feuille Linear dimensions in millimetres Dimensions linéaires en millimétres Consultant's Name Nom de l'expert—conseil

1345 ROSEMOUNT AVENUE CORNWALL ONTARIO CANADA K6J 3E5
TEL.: 613-933-5602 | FAX: 705-936-0335 | WWW.WSP.COM
WSP-5P301-15-0001-001 (WSP# 151-06165-14) Eng. Stamp Sceau de l'ingénieur D. M. SPACEA July 16, 2021

M.CARBONE D.SPACEK

M.CARBONE D.SPACEK

M.CARBONE D.SPACEK

M.CARBONE D.SPACEK

M.CARBONE D.SPACEK

Drawn by Approved
Dessiné par Approuvé

Project title/Titre du projet

26JUNE20

21APR20


Date


511SSM POWERHOUSE STRUCTURAL STABILIZATION PROJECT


Drawing title/Titre du dessin


REFERENCE PHOTOS AND DRAWING 2 OF 2


Designed by/Concept par J.DICERBO/D.SPAC	CEK	Date MAY 25, 2021
Drawn by/Desinné par M.CARBONE		Date MAY 25, 2021
Checked by/Vérifié par J.DICERBO		Date MAY 25, 2021
Approved by/Approuvé par D.SPACEK		Date MAY 25, 2021
	Scale/Échelle VARIES	















REMOVALS PENSTOCK CONCRETE RESERVOIR SECTION
SCALE: 1:150



REMOVALS PENSTOCK CONCRETE RESERVOIR SECTION
SCALE: 1:150

Government Gouvernement of Canada du Canada

Parks Canada

Parcs Canada Unité de gestion du Nord de l'Ontario

KEY PLAN:



SAULT STE. MARIE, ONTARIO

No.	Date	Description	Drawn by Dessiné par	Approved Approuvé
0	21APR20	66% REVIEW	M.CARBONE	D.SPACEK
1	26JUNE20	75% REVIEW	M.CARBONE	D.SPACEK
2	18MAR21	90% REVIEW	M.CARBONE	D.SPACEK
3	25APR21	99% REVIEW	M.CARBONE	D.SPACEK
4	16JULY21	ISSUED FOR TENDER	M.CARBONE	D.SPACEK

Revision / Revision

A Detail number

A Numéro de detail B Numéro de la feuille

Dimensions linéaires en millimétres Linear dimensions in millimetres

Consultant's Name Nom de l'expert—conseil

1345 ROSEMOUNT AVENUE CORNWALL ONTARIO CANADA K6J 3E5
TEL.: 613-933-5602 | FAX: 705-936-0335 | WWW.WSP.COM

WSP-5P301-15-0001-001 (WSP# 151-06165-14)

Eng. Stamp Sceau de l'ingénieur D. M. SPACEA July 16, 2021


Project title/Titre du projet


511SSM POWERHOUSE STRUCTURAL STABILIZATION PROJECT


Drawing title/Titre du dessin


PENSTOCK CONCRETE RESERVOIR AND VALVE CHAMBER CROSS-SECTIONS REMOVALS


Project No./Nº du projet 511SSM  Drawing Set No./Nº de sér	Scale/Échelle AS NOTED  ie du dessin	Sheet No./ N°de la feuille C3.2
Approved by/Approuvé par D.SPACEK		Date MAY 25, 2021
Checked by/Vérifié par J.DICERBO		Date MAY 25, 2021
Drawn by/Desinné par M.CARBONE		Date MAY 25, 2021
J.DICERBO / D.SPAC	CEK	MAY 25, 2021













NOTE: TO BE FIELD MEASURED PRIOR TO FABRICATION OF ANY FITTINGS TO ENSURE PROPER FIT.


## **EXISTING PENSTOCK ELEVATION (APPROX. DIMENSIONS)**



## PENSTOCK ADAPTER PLAN VIEW



# 1 PIPE CONNECTION SECTION (1 OF 2) C4.3 SCALE: 1:25



2 PIPE CONNECTION SECTION (2 OF 2)
C4.3 SCALE: 1:25



Government of Canada Government Gouvernement

Field Unit



du Canada



Parcs Canada Unité de gestion du Nord de l'Ontario





ASSEMBLY SEQUENCE:

BOLT ADAPTER PLATE TO EXISTING PIPE MATCH DRILL THROUGH ADAPTER PLATE, EXISTING PIPE & TEMPORARILY BOLT SO ADAPTER PLATE MATCHES CURVATURE OF EXISTING PIPE.

TACK WELD PLATES TOGETHER. WELD ADAPTER PLATES TO ADAPTER RING.

UNBOLT & REMOVE FOR FINAL SEAL WELD OF ADAPTER PLATES. RE-INSTALL WELDMENT WITH GASKET & BOLT TO EXISTING PIPE.

No.	Date	Description	Drawn by Dessiné par	Approved Approuvé
0	21APR20	66% REVIEW	M.CARBONE	D.SPACEK
1	26JUNE20	75% REVIEW	M.CARBONE	D.SPACEK
2	18MAR21	90% REVIEW	M.CARBONE	D.SPACEK
3	25APR21	99% REVIEW	M.CARBONE	D.SPACEK
4	16JULY21	ISSUED FOR TENDER	M.CARBONE	D.SPACEK

Revision / Revision

A Numéro de detail B Numéro de la feuille

Dimensions linéaires en millimétres Linear dimensions in millimetres

Consultant's Name Nom de l'expert—conseil

1345 ROSEMOUNT AVENUE CORNWALL ONTARIO CANADA K6J 3E5
TEL.: 613-933-5602 | FAX: 705-936-0335 | WWW.WSP.COM

WSP-5P301-15-0001-001 (WSP# 151-06165-14)

Eng. Stamp Sceau de l'ingénieur D. M. SPACER July 16, 2021

Project title/Titre du projet

511SSM POWERHOUSE STRUCTURAL STABILIZATION PROJECT

Drawing title/Titre du dessin

PROPOSED CONTEMPORARY VALVE CHAMBER SECTIONS/DETAILS

Drawn by/Desinné par M.CARBONE		Date MAY 25, 2021
Checked by/Vérifié par J.DICERBO		MAY 25, 2021
Approved by/Approuvé par		Date
D.SPACEK		MAY 25, 2021
D.SPACEK  Project No./No du projet 511SSM	Scale/Échelle AS NOTED	Sheet No./ Nºde la feuille

